

**GOVERNMENT OF MEGHALAYA
MEGHALAYA STATE DISASTER MANAGEMENT AUTHORITY
LACHAUMIERE, MEGHALAYA:::: SHILLONG**

<>0<>

No. SDMA.186/2017/55

Dated Shillong, the 24th Sept, 2026

Quotation Notice

Sealed Quotation in plain paper affixed with non-refundable court fee stamp of ₹ 25/-(Rupees Twenty-Five) only are invited from registered Government Supplier/ Contractors/ Firms for **Establishment of Local Area Network (LAN)** in office of State Disaster Management Authority, Lower Lachauimiere, Meghalaya between **30th September 2026 to 15th October 2026** during office hours. Interested parties are requested to submit the following documents along with the quotation which will be accepted up to 5:00 P.M.

The Quotation will be opened on **16th October, 2026 at 3:00 P.M** in the presence of Quotationers/ Representatives or without.

ESTABLISHMENT OF LOCAL AREA NETWORK (LAN)

(A) Supply (Active Components)

Sl. No.	Items Descriptions	Model Name	UQC	Quantity	Remarks
1	Router - Layer 3 routed ports with ipv4/ipv6 ready, IRU, 1 Modular Interface Slot and 4x1 Gigabit Ethernet WAN ports, x86 CPU with 4GB DRAM default memory and can be upgraded for higher scale and performance with Embedded Software Support / installation / configuration and 1/5 year warranty.		Nos.	1	Users may opt for 5 years warranty with additional cost
2	L2 Managed Switch 10/100/1000 BaseT, 48 Ports 1x4G SFP up-link, interfaces, IPv4 / IPv6 ready, should support switching capacity of 104 Gbps and a forwarding rate of 77.38 Mpps, with installation / Configuration and 1/5 year warranty.		Nos.	1	Users may opt for 5 years warranty with additional cost

(B) SUPPLY (Passive Component) (UTP) For LAN

Sl.No.	Items Descriptions	Model Name	Unit	Qty	Remarks
1	12U Rack		Nos	1	
2	Wire Manager (CAT6A)		Nos	2	
3	24 Port, Cat 6 Jack Panel (Loaded with UTP I/O)		Nos	2	
4	Cat 6 Cable (305 mtrs. per box)		Nos	2	
5	I/O Box (Single SMB)		Nos	7	
6	UTP Patch Cord 1 mtr (CAT 6)		Mtr.	30	
7	UTP Patch Cord 3 mtr (CAT 6)		Mtr.	40	
8	UTP Patch Cord 5 mtr (CAT 6)		Mtr.	5	
9	Supply of marked PVC duct of size (Per Meter) 45 X 25mm		Mtr.	500	
10	Labels for Jack panel / face Plate / Patch Cords (set of 100)		set	1	

(C) INSTALLATION (Passive Component) (UTP) For LAN

Sl.No.	Items Descriptions	Model Name	Unit	Qty	Remarks
1	Installation of 12U Rack		Nos	1	
2	Installation of Wire Manager		Nos	2	
3	Installation of Patch Panel		Nos	2	
4	Installation of marked PVC duct of size (Per Meter) 45 X25mm		Mtr	500	
5	In-Building Laying CAT6 UTP Cable (per mtr)		Nos	540	
6.	Termination of Cat6 / Cat 6A UTP / FTP / SFTP / STP / FFTP Information Outlet (Both End)		Nos	27	
	Installation of Face Plate with the SMB Box		Nos	27	
	Labelling & Dressing of Cat6 / Cat 6A UTP Patch Cords		Nos	27	
7	Testing, Certification & Documentation of Cat6 nodes (Penta-scanner report & documentation)		Nos	27	

(D) Supply (Hardware) (UPS)					
Sl.No.	Items Descriptions	Model Name	Unit	Qty	Remarks
1	Online 1-KVA UPS, with 1/5 year warranty.		Nos	1	Users may opt for 5 years warranty with additional cost

TERMS & CONDITIONS

- 1. Delivery** – The Work should be completed and delivered to the office of the undersigned within stipulated time without extra cost. In case of inability to complete the work, prior intimation should be given to office.
- 2. Condition** – The materials mentioned above should be supplied in good condition and in conformity with the Supply Order. If any variation is found in quantity and quality at the time of delivery, the same will be rejected at your own cost.
- 3. Payment** – Payment will be made after satisfactorily completion of work. Interested firm/ parties can avail necessary details from the Office of the State Disaster Management Authority, Lachaumiere, Shillong.



Executive Director
State Disaster Management Authority
Meghalaya, Shillong

<0>

Memo. No. SDMA.186/2017/ 55(A)

Dated Shillong, the 24th Sept 2026

- Copy to :- 1) The SIO, NIC, Meghalaya, Shillong for uploading the same on the official website www.msdma.gov.in.
- 3) Notice Board
- 4) Office Copy





Executive Director
State Disaster Management Authority
Meghalaya, Shillong

<0>

List of Active & Passive items - Local Area Network
MEGHALAYA STATE DISASTER MANAGEMENT AUTHORITY (MSDMA)
Lachumiere, Shillong-793001, Meghalaya

(A) Supply (Active Components)

Sl.No.	Items Descriptions	UQC	Quantity	Remarks
1	Router - Layer 3 routed ports with ipv4/ipv6 ready, 1RU , 1 Modular Interface Slot and 4x1 Gigabit Ethernet WAN ports, x86 CPU with 4GB DRAM default memory and can be upgraded for higher scale and performance with Embedded Software Support / installation / configuration and 1/5 year warranty.	Nos.	1	<i>Users may opt for 5 years warranty with additional cost</i>
2	L2 Managed Switch 10/100/1000 BaseT, 48 Ports 1x4G SFP up-link interfaces, IPv4 / IPv6 ready, should support switching capacity of 104 Gbps and a forwarding rate of 77.38 Mpps, with installation / Configuration and 1/5 year warranty.	Nos.	1	<i>Users may opt for 5 years warranty with additional cost</i>

(B) SUPPLY (Passive Component) (UTP) For LAN

Sl.No.	Items Descriptions	Unit	Qty	Remarks
1	12U Rack	Nos	1	
2	Wire Manager (CAT6A)	Nos	2	
3	24 Port, Cat 6 Jack Panel (Loaded with UTP I/O)	Nos	2	
4	Cat 6 Cable (305 mtrs. per box)	Nos	2	
5	I/O Box (Single SMB)	Nos	27	
6	UTP Patch Cord 1 mtr (CAT 6)	Mtr.	30	
7	UTP Patch Cord 3 mtr (CAT 6)	Mtr.	40	
8	UTP Patch Cord 5 mtr (CAT 6)	Mtr.	5	
9	Supply of marked PVC duct of size (Per Meter) 45 X 25 mm	Mtr.	500	
10	Labels for Jack panel / face Plate / Patch Cords (set of 100)	set	1	

(C) INSTALLATION (Passive Component) (UTP) For LAN

Sl.No.	Items Descriptions	Unit	Qty	Remarks
1	Installation of 12U Rack	Nos	1	
2	Installation of Wire Manager	Nos	2	
3	Installation of Patch Panel	Nos	2	
4	Installation of marked PVC duct of size (Per Meter) 45 X 25 mm	Mtr.	500	
5	In-Building Laying CAT6 UTP Cable (per mtr)	Nos	540	

6	Termination of Cat6 / Cat 6A UTP / FTP / SFTP / STP / FFTP Information Outlet (Both End)	Nos	27	
	Installation of Face Plate with the SMB Box	Nos	27	
	Labelling & Dressing of Cat6 / Cat 6A UTP Patch Cords	Nos	27	
7	Testing, Certification & Documentation of Cat6 nodes (Penta- scanner report & documentation)	Nos	27	

(D) Supply (Hardware) (UPS)

Sl.No.	Items Descriptions	Unit	Qty	Remarks
1	Online 1-KVA UPS, with 1/5 year warranty.	Nos	1	Users may opt for 5 years warranty with additional cost

Note :

- 1 Positioning of the I/O nodes and switches may change at the time of Installation
- 2 Electrical points (Which are not included in this list of items) are required for UPS to power on the switches..